



- ① FLEXIBLE TREE TIES (MIN. 4 REQUIRED) SECURE TO POLE W/ GALVANIZED NAIL. PLACE TOP TIE IN CANOPY PROTECT BRANCHES FROM DAMAGE.
- ② 2" DIA. X 10' MIN. TREATED LODGEPOLE PINE STAKE (3" DIA. OR 3 GALVANIZED STAKES FOR 36" BOX TREES OR GREATER)
- ③ ROOTBALL - 2" ABOVE FINISHED GRADE, TOP ROOT FLARE SHALL BE VISIBLE
- ④ 2" OF SHREDDED BARK MULCH, 4' DIA. KEEP MULCH 12" CLEAR OF TRUNK. NO LAWN OR SHRUBS IN 4' DIA. ZONE
- ⑤ TEMPORARY 3" WATERING BASIN
- ⑥ BACKFILL MIX: 100% NATIVE SOIL UNLESS THE AGRONOMICAL SOIL REPORT DIRECTS AMENDMENTS
- ⑦ UNDISTURBED NATIVE SOIL, FOOT TAMP ANY OVER EXCAVATION.
- ⑧ REMOVE NURSERY STAKE IMMEDIATELY AFTER PLANTING
- ⑨ FINISH GRADE

#### NOTES:

1. STAKES SHALL NOT PIERCE ROOTBALL & SHALL EXTEND INTO UNDISTURBED SOIL.
2. PLACE FLEXIBLE TREE TIES ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
3. ALL EXCESS SOIL SHALL BE REMOVED FROM THE TOP OF THE ROOT BALL EXPOSING THE ROOT FLARE
4. ROOT PRUNE 1/2" OFF ALL SIDES OF ROOT BALL WITH A SHARP KNIFE.

# TREE PLANTING